

INQUIRIES

Q1: Can the clean soil from the bluff excavation be deposited at the borrow site to replace some of the borrowed material?

A1: No, we do not allow import into the basins.

Q2: Can the project Superintendent also have the duties of Safety Professional?

A2: No.

Q3: Is there a designated disposal site for the bluff excavation material?

A3: No.

Q4: If the bluff excavation material is blended, mixed and/or processed to meet the specified requirements under Contract Specifications Section 02300 paragraph 3.11.1 can it be used for compacted fill buttress?

A4: Yes. We would also evaluate the method of blending to make sure that a consistent material is being produced. Mixing on grade would not be an option.

Q5: Contract Specifications Section 1200 paragraph 1.11.6c states "The borrow area shown on the drawings may be used for additional materials required for the project fills after utilization of the required excavation." This statement is contradictory to Section 2300; please clarify.

A5: See amendment 1

Q6: Contract Specifications Section 01330 paragraph 3.2 references Section 01312 RESIDENT MANAGEMENT SYSTEM (RMS). There is no Section 01312 in the specifications.

A6: See amendment 1

Q7: Do the truck drivers hauling material for the designated borrow site to the project site fall under the Davis Bacon Act? What are the payroll requirements for truck and equipment owner/operators?

A7: Yes.

A7: Section 0850 from the specifications.

Q8: On Section 00010 Bid Item #003, (compaction Fill Buttress) is this line item the material in the area between the existing bank and new finish grade? If so, under what line item do we place the value of work? Do we replace and compact the area between existing bank and the back cut, please advise?

A8: No, Bid Item #003, #0016, and #0023 are shown on sheet 26, on the plans, detail I; where the new fill will be placed. Also, see Measurement & Payment Section 1270 paragraph 1.3.3 page 6 and Section 2300 paragraphs 3.11, 3.12, and 3.13.